



### Bureau of Land Management AZ Magma Mine Preliminary Assessment & Site Inspection

### Magma Consulting

### Final Draft, Work Plan

December 19, 2016

To: Eric Zielske, PE, Environmental Engineer at Bureau of Land Management Bridget Bero, Ph.D, P.E., Grading Instructor

> From: David Finley, Josue Juarez, and Jessica Szaro Undergraduate Environmental Engineering Students

College of Engineering, Forestry, and Natural Sciences Northern Arizona University

> CENE 476: Capstone Prep Fall 2016





# **Table of Contents**

1.0 Introduction
1.1 Project Objectives
1.2 Project Scope7
1.3 Work Plan Schedule7
2.0 Project Management
2.1 Project Management Approach8
2.2 Project Procedures
2.3 Quality Management
2.4 Subcontract Management
3.0 Site Background Information9
3.1 Site Location9
3.2 Site Description
3.3 Previous Operations and Investigation12
4.0 Investigative Approach
4.1 Site Investigation Objective
4.2 Site Investigation General Approach13
5.0 Field Investigation Methods and Procedures13
6.0 Investigative Derived Waste Management13
7.0 Sample Collection Procedures and Analysis13
7.1 Sample Containers, Preservation, and Storage13
7.2 Sample Documentation and Shipment13
7.3 Field Quality Assurance and Quality Control14
8.0 Deviations from the Work Plan14
9.0 PA/SI Reporting
10.0 Project Schedule
11.0 References





Appendix A: Sampling and Analysis Plan	
1.0 Introduction	
1.1 Project Objectives	
2.0 Sampling Rationale	
2.1 Selection of Sampling Locations	
2.2 Selection of Samples for Laboratory Analysis	19
2.3 Selection of Target Metals	19
3.0 Request for Analysis	20
3.1 Analyses Narrative	
3.2 Analytical Laboratory	
3.3 Analytical Methods	21
4.0 Field Methods and Procedures	25
4.1 Team Briefing	25
4.2 Field Equipment	25
4.3 Soil Sample Preparation and Collection	27
4.4 Soil Sample Location Identification	
4.5 Decontamination	
5.0 Investigation Derived Waste Management	
5.1 Water	
5.2 Solid Waste	
6.0 Sampling Containers, Preservation, and Storage	
7.0 Samples Documentation and Shipment	
7.1 Sample Labeling	
7.2 Field Notes and Photographs	
7.3 Sample Chain of Custody Procedures	
8.0 Quality Assurance/Quality Control	
8.1 Laboratory QA/QC	
8.2 Background Samples	
8.3 Data Analysis	
8.4 Data Validation	
9.0 References	





Appendix B: Health and Safety Plan	34
1.0 Introduction	34
2.0 Key Personnel	34
3.0 Hazard Analysis	34
3.1 Responses to Heat Stress	
3.2 Avoiding Falls	
3.3 Encounters with Plant and Animal Life	
4.0 Required Training	
5.0 Decontamination Procedures/Solutions	
6.0 Emergency Information	





# List of Tables

Table A-1: Sampling Design and Rationale	19
Table A-2: Analysis Design and Rationale	
Table A-3: XRF Analysis Procedure – EPA Method 6200	22
Table A-4: Acid Digestion Procedure for GFAA - EPA Method 3050B	23
Table A-5: Acid Digestion Procedure for FIAA - EPA Method 3050B	24
Table A-6: Equipment and Supplies for Sampling	25
Table A-7: Surface Soil Sampling Procedure	27
Table A-8: Decontamination Procedure	28
Table B-1: Job Hazard Analysis	34
Table B-2: KRMC Contact Information	37
Table B-3: Directions from AZ Magma Mine to KRMC	37

# List of Figures

Figure 3-1: AZ Magma Mine in Reference to Chloride and Kingman	9
Figure 3-2: AZ Magma Mine's Proximity to Chloride	10
Figure 3-3: Current Condition of Tailings	10
Figure 3-4: Tailings in the Wash	11
Figure 3-5: Tailings on the Road	11
Figure 3-6: Wells Near AZ Magma Mine	12
Figure A-1: Grid Sampling for AZ Magma Mine	17
Figure A-2: Detail View of Sampling Grid	18
Figure A-3: Blank Chain of Custody Form	30
Figure B-1: Map from AZ Magma Mine to KRMC	38





# List of Abbreviations

BLMBureau of Land ManagementCOCContaminant of ConcernFIAAFlame Ionization Atomic AbsorptionGFAAGraphite Furnace Atomic AbsorptionGISGeographic Information SystemGPSGlobal Positioning SystemHASPHealth and Safety PlanHAZWOPERHazardous Waste Operations and Emergency ResponseIDWInvestigation Derived WastesKRMCKingman Regional Medical CenterNAUNorthern Arizona UniversityPAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite InspectionSDLSail Demediation Laurel	AA	Atomic Absorption
FIAAFlame Ionization Atomic AbsorptionGFAAGraphite Furnace Atomic AbsorptionGISGeographic Information SystemGPSGlobal Positioning SystemHASPHealth and Safety PlanHAZWOPERHazardous Waste Operations and Emergency ResponseIDWInvestigation Derived WastesKRMCKingman Regional Medical CenterNAUNorthern Arizona UniversityPAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSite Inspection	BLM	Bureau of Land Management
GFAAGraphite Furnace Atomic AbsorptionGISGeographic Information SystemGPSGlobal Positioning SystemHASPHealth and Safety PlanHAZWOPERHazardous Waste Operations and Emergency ResponseIDWInvestigation Derived WastesKRMCKingman Regional Medical CenterNAUNorthern Arizona UniversityPAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	COC	Contaminant of Concern
GISGeographic Information SystemGPSGlobal Positioning SystemHASPHealth and Safety PlanHAZWOPERHazardous Waste Operations and Emergency ResponseIDWInvestigation Derived WastesKRMCKingman Regional Medical CenterNAUNorthern Arizona UniversityPAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	FIAA	Flame Ionization Atomic Absorption
GPSGlobal Positioning SystemHASPHealth and Safety PlanHAZWOPERHazardous Waste Operations and Emergency ResponseIDWInvestigation Derived WastesKRMCKingman Regional Medical CenterNAUNorthern Arizona UniversityPAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	GFAA	Graphite Furnace Atomic Absorption
HASPHealth and Safety PlanHAZWOPERHazardous Waste Operations and Emergency ResponseIDWInvestigation Derived WastesKRMCKingman Regional Medical CenterNAUNorthern Arizona UniversityPAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	GIS	Geographic Information System
HAZWOPERHazardous Waste Operations and Emergency ResponseIDWInvestigation Derived WastesIDWInvestigation Derived WastesKRMCKingman Regional Medical CenterNAUNorthern Arizona UniversityPAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	GPS	Global Positioning System
IDWInvestigation Derived WastesKRMCKingman Regional Medical CenterNAUNorthern Arizona UniversityPAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	HASP	Health and Safety Plan
KRMCKingman Regional Medical CenterNAUNorthern Arizona UniversityPAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	HAZWOPER	Hazardous Waste Operations and Emergency Response
NAUNorthern Arizona UniversityPAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	IDW	Investigation Derived Wastes
PAPreliminary AssessmentPPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	KRMC	Kingman Regional Medical Center
PPEPersonal Protective EquipmentQAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	NAU	Northern Arizona University
QAQuality AssuranceQCQuality ControlSAPSampling and Analysis PlanSISite Inspection	PA	Preliminary Assessment
QCQuality ControlSAPSampling and Analysis PlanSISite Inspection	PPE	Personal Protective Equipment
SAPSampling and Analysis PlanSISite Inspection	QA	Quality Assurance
SI Site Inspection	QC	Quality Control
•	SAP	Sampling and Analysis Plan
CDI Coil Domodiation Loval	SI	Site Inspection
SRL Soli Remediation Level	SRL	Soil Remediation Level
XRF X-ray Fluorescence	XRF	X-ray Fluorescence





## **1.0 Introduction**

Magma Consulting will conduct a field investigation at the AZ Magma Mine for the Bureau of Land Management (BLM) to determine contaminants at the site and possible risks they pose to the public. This Work Plan details a Sampling and Analysis Plan (SAP) and a Health and Safety Plan (HASP). It is developed specifically for the field investigation, including sampling techniques, data collection, and sample analysis.

The purpose of the SAP is to describe sampling objectives, locations, procedures, quality assurance and control, and analysis, including X-ray fluorescence (XRF) and acid digestion. This SAP specifically describes details for only surface soil samples from the mine. The SAP can be found in Appendix A of this document.

The purpose of the HASP is to include safety control measures and emergency information to consider during the field investigation. The HASP can be found in Appendix B of this document.

### **1.1 Project Objectives**

The objective of the field investigation is to obtain physical, chemical, and analytical data to support evaluations and decisions made within the preliminary assessment and site inspection (PA/SI). The PA/SI will contain a human and ecological risk assessment to determine the risk of the site for humans, plants, and animals. Thus, the data quality objectives are to obtain data of quality acceptable for screening-level assessment/decision making.

### 1.2 Project Scope

The field work at AZ Magma Mine and analysis in the lab will include:

- Completion of a Work Plan containing a SAP and HASP.
- Collect up to 100 surface soil samples at the mine, including background and hotspot samples.
- Analyze all samples through XRF analysis to determine concentrations of the contaminants of concern (COC).
- Analyze 20% of samples through atomic absorption to correlate with XRF results.
- Completion of a PA/SI to determine risk at the site.

### 1.3 Work Plan Schedule

The Work Plan (including the SAP and HASP), completed December 2016, details sampling and analysis to be performed January to May 2017. Surface sampling will occur January 20-21, 2017. If requested by BLM, summary reports of data analyses can be submitted throughout this time period. Otherwise, data collected according to the SAP will be reported in the PA/SI. The PA/SI will be completed by May 2017.





### 2.0 Project Management

#### 2.1 Project Management Approach

To ensure project organization, team roles were assigned with responsibilities attached to each role. The Project Manager is responsible for overall management and coordination of the team and must maintain communications with the BLM contact, Eric Zielske, Technical Advisor Taylor Oster, and Grading Instructor Bridget Bero. The Health and Safety Specialist is responsible for ensuring the HASP is followed explicitly in the field. The Lab Analysis Lead is responsible for maintaining quality assurance and control during lab analysis.

### 2.2 Project Procedures

All procedures detailed in this Work Plan follow American Society for Testing and Materials (ASTM) standard operating procedures or Environmental Protection Agency (EPA) Methods. All personnel working in the field or lab must follow procedures implicitly. Oversight of all personnel will be the responsibility of Bridget Bero. Field and lab procedures are detailed in the SAP (Appendix A).

#### 2.3 Quality Management

Quality will be managed by Bridget Bero, the Northern Arizona University (NAU) person-incharge, in the field through following all procedures detailed in the SAP. Quality assurance and quality control (QA/QC) are detailed in Section 8.0 of the SAP (Appendix A).

#### 2.4 Subcontract Management

A subcontract for this project includes atomic absorption (AA) analysis completed by the NAU Chemistry Lab located in the Wettaw Building. All subcontract management will be the responsibility of the project manager, including communication with Jeffrey Propster, a research specialist at NAU, and transportation of the samples to the lab. Further discussion of what work will be subcontracted is detailed in section 3.2.3 of the SAP (Appendix A).





## 3.0 Site Background Information

This section provides a summary of the site location and previous operations that occurred at the site.

### 3.1 Site Location

The Arizona Magma Mine (Latitude N 35°25'00" Longitude W114°13'27") is located approximately one mile west of Chloride, Arizona with a population of 250 residents (McNeely, 2016). The mine is also located 28 miles north of Kingman, with a population of nearly 30,000 (ADMMR, 1995). Figure 3-1 shows the mine's location in reference to both towns and Figure 3-2 shows its proximity to Chloride.




Figure 3-1. AZ Magma Mine in Reference to Chloride and Kingman (Google Earth, 2016)








Figure 3-2. AZ Magma Mine's Proximity to Chloride (Google Earth, 2016)

### **3.2 Site Description**

The site belongs to the BLM and is considered open and accessible to the public. While mine operations shut down in the early 1940's, tailings about 10 feet deep are still present on the site (Zielske, 2016). These tailings may contain lead or arsenic (Zielske, 2016). A photo of the tailings can be seen in Figure 3-3.



Figure 3-3. Current Condition of Tailings (Zielske, 2016)





The tailings have also washed down into the nearby wash (Figure 3-4) and onto the road that connects the mine to Chloride (Figure 3-5).



Figure 3-4. Tailings in the Wash (Zielske, 2016)



Figure 3-5. Tailings on the Road (Zielske, 2016)





The site is also located near several water wells, as seen in Figure 3-6. Wells are signified by red dots on the map.




Figure 3-6. Wells Near AZ Magma Mine (ADWR, 2016)

The depth to groundwater for these wells varies from 100 to 150 feet and may be at risk for contamination from the mine (ADWR, 2016).

### 3.3 Previous Operations and Investigation

Mining began at this site, originally called Arizona Diana Mine, around 1890. It experienced a period of inactivity until the 1920's where its commodities were primarily silver, gold, and lead (ADMMR, 1995). The mine closed again in the 1920's and was reopened and named after its new operating company, Magma Mine, in 1934 (ADMMR, 1995). For the mine's reopening, a new mill was built that was initially reported to provide a steady stream of revenue for years to come. However, after an investigation in 1940, it was found to be run down and in need of repair (ADMMR, 1995). A high-grade ore with ruby silver was mined at the site in its early years, while a low-grade ore with zinc and lead was its primary export in its later years. The mine was reviewed several times from 1940 to 1945 due to lack of funding and difficulty in extracting anything lucrative. As a result of these site investigations, Arizona Magma Mine was advised to close in 1945. The site has been inactive ever since, however, there have been no site investigations completed during this time.





## 4.0 Investigative Approach

This section discusses the objectives and approach of the site investigation.

#### 4.1 Site Investigation Objective

The objective of this site investigation is to collect and analyze soil samples from AZ Magma Mine for possible COCs to use in a screening level risk assessment. Further discussion of the site investigation objectives can be seen in Section 1.1 of the SAP (Appendix A).

#### 4.2 Site Investigation General Approach

The site investigation approach includes sample collection of surface soil at the mine site following all procedures detailed in the SAP. The samples will then be analyzed using XRF and AA analysis.

## **5.0 Field Investigation Methods and Procedures**

The field investigation methods and procedures are detailed in Section 4.3-4.5 of the SAP (Appendix A). These procedures will be followed exactly how they are written to ensure QA/QC.

## 6.0 Investigative Derived Waste Management

Investigative Derived Waste (IDW) will include, but is not limited to soil and sediment, decontamination fluids, and disposable sampling equipment/PPE. How these wastes will be managed is detailed in Section 5.0 of the SAP (Appendix A).

## 7.0 Sample Collection Procedures and Analysis

This section describes how samples will be collected, stored and labeled, as well as QA/QC in the field.

#### 7.1 Sample Containers, Preservation, and Storage

The samples will be collected using hand trowels and stored in labeled, gallon-sized plastic bags. A detailed description of sample containers and storage is in Section 6.0 of the SAP (Appendix A).

### 7.2 Sample Documentation and Shipment

All samples collected will be documented in the field notes by all participating members of the field investigation. This documentation will include the location of the sample (grid number and





picture), who took the sample, what kind of sample it is, etc. The soil samples will be transported from the site to NAU in storage totes. An in-depth description of logbooks and sample transport is detailed in Section 7.0 of the SAP (Appendix A).

### 7.3 Field Quality Assurance and Quality Control

To ensure quality assurance and control in the field, samples will be collected following the exact procedures detailed in the SAP (Appendix A). Background samples will also be taken to compare the mine site soil with surrounding soils. To ensure quality assurance and control while analyzing the soil samples in the lab, all QA/QC procedures and considerations from EPA Method 6200 (Field Portable X-Ray Fluorescence Spectrometry for the Determination of Elemental Concentrations in Soil and Sediment) and EPA Method 3050B (Acid Digestion of Sediments, Sludges, and Solids) will be followed. Further discussion of field and lab quality assurance and control is detailed in Section 8.0 of the SAP (Appendix A).

## 8.0 Deviations from the Work Plan

All deviations from the Work Plan will be recorded in the field logbook and must be approved by the on-site supervisor, Bridget Bero. The documentation will include what the deviation was and the rationale for the change. Further discussion on how to deal with deviations can be seen in Section 4.1 of the SAP (Appendix A).

# 9.0 PA/SI Reporting

The preliminary assessment and site inspection for this site will be completed after samples are collected and analyzed for COCs concentrations and a human and ecological risk assessment is finished. These documents will include human and ecological risk assessments to determine the risk these COCs pose to any humans that will come into contact with the site. If the COCs are above the action level and pose a serious risk, further action should be taken by the BLM.

# **10.0 Project Schedule**

The activities and analysis discussed in this Work Plan will be completed during the winter and spring of 2017 (January 20 - May 5). Activities include training, sampling, lab analysis, analytical analysis, risk assessment, geographic information system (GIS) analysis, and documentation of the PA/SI.





### 11.0 References

- Arizona Department of Mines and Mineral Resources File Data (ADMMR), "Arizona Magma," September 1995.
- Arizona Department of Water Resources (ADWR), "Well registry web map,". [Online]. Available: https://gisweb.azwater.gov/WellRegistry/Default.aspx. Accessed: Sep. 17, 2016.

Google Earth, "AZ Magma Mill," 35°25'00" N 114°13'27" W, Accessed: September 19, 2016.

McNeely J., "Chloride History," [Online]. Available: http://www.chlorideaz.com/history.html. Accessed: September 17, 2016.

Zielske E., BLM Client interview, September 7, 2016.





# Appendix A

### Sampling and Analysis Plan AZ Magma Mine Site

# **1.0 Introduction**

This Sampling and Analysis Plan (SAP) details sampling that will occur at the AZ Magma Mine located on Bureau of Land Management (BLM) land, as well as all analysis that will be completed on the soil samples taken from the site. Selection of sampling locations on site and laboratory analysis is explained and detailed. An aligned grid of the mine is provided, with a discussion of the number and type of samples to be taken in each grid. Field methods are also provided to describe how the team is to collect, preserve, store, document, and transport samples. Quality control (QC) is also discussed, including the use of background samples and data correlation to ensure the results are legitimate.

### **1.1 Project Objectives**

The purpose of this site inspection is to collect and analyze soil samples from AZ Magma Mine located near Chloride, Arizona for possible contaminants of concern (COC). The data obtained from this inspection will be used as screening level data for the BLM to determine if further action should be taken at this site. If the COCs, discussed in Section 2.3 the SAP, are above their respective action levels, further action should be taken.

# 2.0 Sampling Rationale

This section discusses the sampling locations and the rationale for each, including general samples, hotspot, and background samples. The samples that will be chosen for analysis are also included in this section, as well as the COCs that may be expected at this site.

### 2.1 Selection of Sampling Locations

The sampling grid that will be used during sampling can be seen below in Figure A-1. A detail view of the sampling grid can be seen in Figure A-2. The large grid spacing is located on the main tailings and is 100 feet by 100 feet. The small grid spacing is within the wash and onto the road near the mine and is 40 feet by 40 feet. The large grid nodes are labeled left-to-right, top-to-bottom. The small grid nodes are labeled left-to-right, top-to-bottom. The small grid nodes. A total of 100 samples will be taken throughout the whole site, including grid, hotspot, and background samples. Hotspot and background samples will be chosen at the site with oversight from supervisor Bridget Bero. Table A-1 lists the sampling location, ID number of the sample, and the rationale for that sample. Information on the ID





number format for all samples can be seen in Section 4.4 of the SAP. All sample types will be surface samples to avoid digging into the 10-foot deep tailings.




Figure A-1. Grid Sampling for AZ Magma Mine (Google Maps, 2016)








Figure A-2. Detail View of Sampling Grid





Sampling Location	ID Number	Rationale
Main Tailings Pile	GN1 - GN25	Concentrations within the main tailings pile will be consistent, so a larger grid spacing and smaller amount of samples is appropriate.
The Wash	GN26 - GN55, GN77 - GN91	Concentrations within the wash will vary as distance from the main tailings site increases, so a smaller grid and more frequent sampling amount is appropriate.
The Road	GN56 - GN76	Concentrations on the road will vary depending on the side of the road and distance from main tailings.
Hotspot Samples - Various Locations	HS1 - HS5	Hotspot samples will be chosen by Bridget Bero in the field at areas of observed tailings. These samples will be representative of the highest concentrations of COCs at the site.
Background Samples - Various Locations	BG1 – BG4	Background samples will be chosen by Bridget Bero in the field as appropriate. These samples will be used to identify the naturally occurring levels of COCs in the area surrounding the site.

#### 2.2 Selection of Samples for Laboratory Analysis

All samples will be analyzed using X-ray fluorescence (XRF). 20% of these samples will also be analyzed by atomic absorption (AA). Samples with high, low, and average concentrations of the COCs will be selected for AA analysis. Discussion of the methods for these analyses can be seen in Section 3.0.

### 2.3 Selection of Target Metals

Possible COCs derive from the type of mining that occurred at the site. The AZ Magma Mine was primarily used for silver, gold, and lead mining from the 1890's to the late 1930's (ADMMR, 1995). Thus, potential COCs at the site include but are not limited to lead and arsenic (Zielske, 2016).





## 3.0 Request for Analysis

This section discusses the analytical support for the project. This includes the analyses requested by BLM, possible turnaround times, available resources and laboratories for the team, and method numbers and descriptions for analyses.

#### 3.1 Analyses Narrative

The required analyses and procedures for this investigation include drying, sieving, XRF, acid digestion, and AA. Drying is required so that all material can be properly sieved. All samples will be dried and sieved prior to XRF analysis. Table A-2 shows how sampling will be dispersed among grid, hotspot, and background samples.

Sampling Location	ID Number	Number of Samples (XRF)
Main Tailings Pile	GN1 - GN25	25
The Wash	GN26 - GN55, GN77 - GN91	45
The Road	GN56 - GN76	21
Hotspot Samples - Various Locations	HS1 - HS5	5
Background Samples - Various Locations	BG1 – BG4	4
Total # of Samples		100

#### Table A-2. Analysis Design and Rationale

#### **3.2 Analytical Laboratory**

All sieving, XRF analysis, and acid digestion with be done in the Environmental Engineering Lab of the Engineering Building. All AA analysis will be done in the NAU Chemistry Lab of the Wettaw Building.





### **3.3 Analytical Methods**

This section identifies and briefly describes the methods used for all preparatory and analytical processes required for this investigation.

#### 3.3.1 Drying and Sieving Procedure

Prior to analysis, all soil samples will be dried for 24 hours at 100°F in a drying oven. All samples will be sieved to a #200 sieve to homogenize the samples. The samples will be put into the sieve from their original storage gallon bag (see Section 4.3). Once in the sieve stack, the sieves will be placed into a shaker for approximately five minutes. After the shaker, the soil will be put back into its gallon bag to be analyzed. The sieves must be thoroughly cleaned with a soft bristle brush between every sample analysis.

#### 3.3.2 X-Ray Fluorescence Spectrometry

The method to be followed for XRF analysis is the Environmental Protection Agency's (EPA) Method 6200. This method is specified for XRF analysis in the field, but all analysis for this investigation will be completed in the Environmental Engineering Lab following sample collection. The procedures for the method are the same despite this difference.

EPA Method 6200 is applicable for 26 analytes, including the potential COCs mentioned in Section 2.3 (EPA, 2007). XRF technology irradiates a soil sample with x-rays and dislodges inner shell electrons, causing outer shell electrons to cascade and fill in their place. This rearrangement results in emissions of x-rays for that atom/contaminant. These x-rays that come back to the XRF facilitate in the measurement of the contaminant in that soil sample (EPA A, 2007). The steps to follow for XRF analysis from EPA Method 6200 are summarized in Table A-3.





#### Table A-3. XRF Analysis Procedure - EPA Method 6200

Step	Description
1.	Make sure the bag is flat and the soil in the bag is evenly dispersed, then mark the bag with a 3x3 grid to separate it into 9 sections. Each section will be analyzed using the XRF one time (i.e. 9 samples per gallon bag).
2.	Place the gallon bag on the floor of the lab.
3.	Turn the XRF on and ensure it is in in situ mode. Enter the sample name, location, and team member responsible for analysis.
4.	Place the instrument directly on top of the section of the bag containing the soil sample to analyze.
5.	Pull the trigger with the device touching the bag. Keep the trigger pulled down for the entire 90 second time period. After 90 seconds, the light will flash and the shutter will close. Do not remove the XRF from the sample until the shutter is closed. Repeat for each of the 9 sections following a top left to bottom right pattern.
6.	Review the concentrations on the screen and transfer them from the XRF device to a spreadsheet on a laptop or desktop computer.
7.	Discard the single lowest and single highest values from the 9 collected values. Average the remaining for each COC.

#### 3.3.3 Acid Digestion

An acid digestion must be completed before the samples are sent to a lab for AA analysis. If trace metals, like arsenic, lead, nickel, etc. are found, Graphite Furnace Atomic Absorption (GFAA) will be completed (NAU, 2016). If base cations, like sodium and potassium, or major metals, like zinc and iron, are found, Flame Ionization Atomic Absorption (FIAA) will be completed (NAU, 16). Only 20% of the samples (20 samples) will go through AA analysis. The method to be followed for acid digestion is EPA Method 3050B (Acid Digestion of Sediments, Sludges, and Soils). This method, although not a total digestion, is effective and will dissolve almost all elements that could become environmentally available (EPA B, 1996).





The procedure for acid digestion to prepare samples for GFAA from EPA Method 3050B is summarized in Table A-4.

Table A-4. Acid Digestion Procedu	re for GFAA - EPA Method 3050B

Step	Description
1.	Transfer a 1-2 gram sample (wet weight) or 1 gram (dry weight) to a digestion vessel.
2.	Add 10 mL of 1:1 HNO3 to the sample, mix, and cover. Heat the sample to $95^{\circ}C \pm 5^{\circ}C$ and reflux, or boil so the vapor returns to the liquid after condensing, for 10 to 15 minutes. Allow the sample to cool, add 5 mL of HNO3, replace cover, and reflux at same temperature for 30 minutes. Repeat this step until no brown fumes are given off by the sample. Allow the solution to evaporate to approximately 5 mL without boiling, or heat at $95^{\circ}C \pm 5^{\circ}C$ for two hours. Ensure the solution is covered at all times.
3.	Allow sample to cool. Add 2 mL of water and 3 mL of 30% H <sub>2</sub> O <sub>2</sub> . Cover the vessel and return to the heat source to begin peroxide reaction. Heat until effervescence subsides, remove the vessel from the heat source, and let it cool.
4.	Continue to add $30\%$ H <sub>2</sub> O <sub>2</sub> in 1-mL increments until effervescence is minimal or until the sample appearance is unchanged. <b>Do not</b> add more than a total of 10 mL.
5.	Cover the vessel and heat until the volume is reduced to 5 mL, or heat at 95°C $\pm$ 5°C for two hours. Ensure the solution is covered at all times.
6.	Let the sample cool and then dilute to 100 mL with water. Particulates in the dilute solution should be removed by filtration, centrifugation, or settling. 6a. Filter through Whatman No. 41 filter paper. 6b. Centrifugation at 2,000-3,000 rpm for 10 minutes.
7.	The sample is now ready to be sent to the lab for GFAA.





The procedure for acid digestion to prepare samples for FIAA from EPA Method 3050B is summarized in Table A-5.

Step	Description
1.	Transfer a 1-2 gram sample (wet weight) or 1 gram (dry weight) to a digestion vessel.
2.	Add 10 mL of 1:1 HNO3 to the sample, mix, and cover. Heat the sample to $95^{\circ}$ C $\pm 5^{\circ}$ C and reflux, or boil so the vapor returns to the liquid after condensing, for 10 to 15 minutes. Allow the sample to cool, add 5 mL of HNO3, replace cover, and reflux at same temperature for 30 minutes. Repeat this step until no brown fumes are given off by the sample. Allow the solution to evaporate to approximately 5 mL without boiling, or heat at $95^{\circ}$ C $\pm 5^{\circ}$ C for two hours. Ensure the solution is covered at all times.
3.	Allow sample to cool. Add 2 mL of water and 3 mL of $30\%$ H <sub>2</sub> O <sub>2</sub> . Cover the vessel and return to the heat source to begin peroxide reaction. Heat until effervescence subsides, remove the vessel from the heat source, and let it cool.
4.	Continue to add $30\%$ H <sub>2</sub> O <sub>2</sub> in 1-mL increments until effervescence is minimal or until the sample appearance is unchanged. <b>Do not</b> add more than a total of 10 mL.
5.	Cover the vessel and heat until the volume is reduced to 5 mL, or heat at $95^{\circ}C \pm 5^{\circ}C$ for two hours. Ensure the solution is covered at all times.
6.	Add 10 mL HCl to the sample prepared in previous steps. Cover and place the vessil into the heating source to reflux at $95^{\circ}C \pm 5^{\circ}C$ for 15 minutes.
7.	Filter the solution through Whatman No. 41 filter paper (or something equivalent to that) and collect the filtrate in a 100-mL volumetric flask.
8.	The sample is now ready to be sent to the lab for FIAA.

#### Table A-5. Acid Digestion Procedure for FIAA - EPA Method 3050B

#### **3.3.4 Atomic Absorption**

The team will send the 20 samples that experienced acid digestion to the NAU Chemistry Lab located in the Wettaw Building for AA analysis. This analysis is completed as a confirmatory analysis by finding a correlation to confirm the XRF values found in earlier analyses. As the AA is subcontracted, direct methods and procedures will not be found in this SAP. A brief summary of the process is provided below.





A beam of electromagnetic radiation from excited atoms (lead, arsenic, etc.) is passed through the sample (Royal Society of Chemistry). Some of that radiation will be absorbed by the sample. The more of the atoms in the sample, the more radiation is absorbed. A calibration curve is then constructed to compare known atom concentrations with the measured concentration. The concentration of the possible COCs will then be sent back to the team to compare to XRF data.

## 4.0 Field Methods and Procedures

### 4.1 Team Briefing

Prior to sampling, all personnel will be briefed on sampling procedures, necessary personal protective equipment (PPE), calibration procedures, logging procedures, and decontamination procedures. No personnel will be permitted to work on-site without full understanding of all procedures and precautionary measures. The Health and Safety Plan (HASP) (Appendix B) details all safety considerations for this investigation.

### 4.2 Field Equipment

Table A-6 shows the equipment necessary to sample the soil.

General Supplies		
Supply/Equipment	Use	Quantity
Site map and aerial photos	Used to identify sampling locations	6
Black Sharpies	Used to write on sampling containers	5
Field logbooks (Rite in the Rain Environmental)	Used to log field notes and observations	1
Handheld global positioning system (GPS) unit	Used to track sampling coordinates	1
Digital camera	Used to take photographs of sampling locations	2

#### **Table A-6.** Equipment and Supplies for Sampling





Sample Collection Supplie	es	
Supply/Equipment	Use	Quantity
Trowel	Used to collect samples	4
Custody tape	Used to indicate sample tampering, will seal boxes that hold numerous samples	2 rolls
Custody forms	Used to list numerous samples in a single box container, will be placed in box container	8 forms
1-gallon plastic bags	Used to contain samples	250 pack, 1 per sample, spares in case of tears
Sample Location Surveyir	g and Documentations	-
Supply/Equipment	Use	Quantity
Compass	Used to determine direction	2
Measuring tape	Used to measure distances between sampling locations	2
Surveying stakes/flags	Used to mark sampling locations	100 total, 1 per sample
Decontamination Supplies	; ;	-
Supply/Equipment	Use	Quantity
5-gallon decontamination waste bucket	Used to contain waste liquid	3
Bottles for distilled water, 16 oz	Used to clean sampling equipment	4 bottles
Paper towels	Used to dry sampling equipment	3 rolls
Dish soap, 1 oz	Used to clean sampling equipment	1 bottle
Scrub brushes	Used to clean sampling equipment	2





Personal Protective Equipn	nent	
Supply/Equipment	Use	Quantity
Tyvek suits (come with overboots)	Used to protect the sampling team from exposure to contaminants	12 total, 1 per person per day, 2 spares
Nitrile gloves	Used to protect the user from exposure to contaminants, spare gloves will be brought in the event any gloves tear	400 total, 1 per person per sample

#### 4.2.1 Calibration of Field Equipment

The handheld GPS unit will be calibrated in accordance with the frequency and methods suggested by the manufacturer. All calibration procedures will be recorded in the project logbook as deemed necessary. The GPS must be calibrated to  $\pm 5\%$  of the manufacturer's standard. Failure to do so will result in invalidation of sampling identification (ID) numbers (AMEC, 2010). Prior to departing for the site, the GPS and the camera will be tested to verify they work.

#### 4.3 Soil Sample Preparation and Collection

Surface soil sampling will be conducted using the procedures detailed in Table A-7.

Step	Description
1.	Remove surface litter (vegetation, large rocks/pebbles).
2.	Collect surface soil sample using trowel. Surface soil samples will be collected at a maximum depth of 3 inches.
3.	Each sample will be placed into a 1-gallon plastic bag and labeled. Approximately half of the bag's volume will be filled with soil. The logbook will record the person taking the sample, location, grid number, and date/time taken.





#### 4.4 Soil Sample Location Identification

Each sample will be assigned a unique ID number that corresponds to the location it was taken from. It will be permanently marked on the sample container with the following format: AZMG-type-#, where:

- AZMG identifies the location (AZ Magma Mine)
- Type of sample = GN for grid node, HS for hotspot, BG for background
- # corresponds to the particular sample for a sample type (1, 2, 3...)

#### 4.5 Decontamination

Sampling equipment intended for reuse shall be decontaminated using the procedures detailed in Table A-8.

Step	Description
1.	Place equipment in 5-gallon bucket.
2.	Scrub equipment with dish soap and water.
3.	Rinse the equipment with distilled or deionized water in a second clean bucket.
4.	Dry equipment on a clean surface with paper towels and store in a third clean bucket.

#### Table A-8. Decontamination Procedure

## **5.0 Investigation Derived Waste Management**

Whenever possible, generation of investigation derived wastes (IDW) will be minimized. IDW includes, but is not limited to, soil and sediment, decontamination fluids, and disposable sampling equipment/PPE (Stroh, 2012).

#### 5.1 Water

Decontamination fluids will be discharged on-site.

#### 5.2 Solid Waste

Disposable sampling equipment and PPE will be treated as a solid waste and disposed of in appropriate containers (Stroh, 2012). Containers with disposable equipment will be shipped back to NAU for proper disposal.

Soil samples below Arizona's residential soil remediation levels (SRLs) will be disposed of as solid waste. Soil samples above Arizona's residential SRLs will be retained for further use in the Environmental Engineering Lab or disposed of as hazardous waste per NAU Risk Management protocols.





## 6.0 Sampling Containers, Preservation, and Storage

All individual soil samples will be placed in 1-gallon plastic bags, which will be stored in plastic boxes. Samples will be double bagged if leaks/breaks are observed in the original bag. The samples will remain in the boxes until transported to the NAU campus. No preservation additives are necessary for soil samples in this operation. The holding time for all samples is 6 months, after which the samples are no longer valid (MDH, 2013).

### 7.0 Samples Documentation and Shipment

This section describes procedures for sample labeling, logbook field notes, chain of custody, and sample shipment.

### 7.1 Sample Labeling

The sequential ID number for each sample will be written on the 1-gallon plastic bag it is collected in. See Section 4.4 of the SAP for further information.

#### 7.2 Field Notes and Photographs

For each sample, the following information will be logged in a field notebook:

- The sample's ID number
- Time at which the sample was taken
- The person who took the sample
- Visual characteristics of sample
- Other relevant observations

A photograph of each sample before and after excavation will be taken.

#### 7.3 Sample Chain of Custody Procedures

The boxes containing numerous bags of samples will be sealed with tape when full. A Chain of Custody form listing all samples in the box will be placed in each box prior to sealing.

For samples sent to the NAU Chemistry Lab for AA analysis, the Chain of Custody form will accompany the samples. This form will inform the lab technician of the analyses requested for each soil sample. A blank version of the Chain of Custody form to be used is presented in Figure A-3.





_									
	Team Name:		Billing Inf	Information:	_		An	Analysis / Container / Preservative	ervative
	Magma Consulting	бı							
	Report to:		City/State	City/State Collected:					
	Jessica Szaro, Project Manager	Manager							
	email: jas843@nau.edu	,	Chloride, AZ	e, AZ					
	phone: (520) 519-9370								
	Sample ID	Comp/Grab	Matrix	Collected by	Date	Time			
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
	AZMG-	Grab							
ody	Relinquished by: (Signature)	Date:	Time:	Recieved by: (Signature)	Date:	Time:	Temperature Recieved:		
Form									
ו	Relinquished by: (Signature)	Date:	Time:	Recieved by: (Signature)	Date:	Time:			
	Relinquished by: (Signature)	Date:	Time:	Recieved by: (Signature)	Date:	Time:	COC Seal Intact (Y/N):		
	Relinquished by: (Signature)	Date:	Time:	Recieved for lab by: (Signature)	Date:	Time:			





## 8.0 Quality Assurance/Quality Control

The quality assurance/quality control (QA/QC) plan has been developed to ensure that sample collection and data obtained are reliable and produces trustworthy results. The procedures described in the following sections ensure that field sampling, laboratory analysis, and statistical analyses will meet the data quality objectives. Failure to properly collect samples or failure to properly conduct the laboratory analysis will introduce uncertainty, reducing the reliability of the data (AMEC, 2010).

### 8.1 Laboratory QA/QC

QA/QC in the laboratory will be ensured through the use of standard operating procedures, frequent inspection, and complete documentation of all laboratory activities. All sample drying will be documented in a lab notebook. If necessary, a dried sample will be placed in a new plastic bag and properly labeled if the original bag contains excessive moisture. For soil sieving, each sieve will be properly cleaned and decontaminated between individual uses. All sieving will be documented in a lab notebook. For XRF analysis, all data will be recorded in a lab notebook. The highest and lowest values from an individual sample (which are excluded from the sample average, see Table A-3) will be identified in the lab notebook.

The analytical laboratory that will be contracted for the AA analysis will be asked to provide the following information in support of QA/QC (AMEC, 2010):

- Analytical method
- Method detection limit
- Practical quantitation limit
- Units of measure
- Sample collection and analysis dates
- Adherence to designated holding time
- Method blank results
- Laboratory duplicate results and relative percent difference
- Initial and continuing calibration checks

#### 8.2 Background Samples

Background sampling will be taken from undisturbed natural areas outside of the waste site. These samples are collected in order to understand what the naturally occurring levels of the COCs are (Innis 24).

#### 8.3 Data Analysis

XRF data will be compared to AA data using least squares linear regression. If any measured concentrations span more than one order of magnitude, the data will be log transformed. The correlation coefficient obtained from the regression analysis must be at least 0.7 for the XRF data to be suitable in a screening level risk assessment.





#### 8.4 Data Validation

Data validation is intended to identify unreliable/invalid laboratory measurements caused by improper sample collection procedures or analytical laboratory methods. Data validation will follow the guidelines set by the EPA for inorganics. The following steps will be taken to validate laboratory analytical data (AMEC, 2010):

- Chain of Custody forms and laboratory reports will be checked to ensure that the samples were analyzed for the correct parameters and methods. Samples that were not analyzed with the correct method or the correct contaminant will be flagged.
- Samples that have a dissolved metal concentration that is larger than the total metal concentration will be flagged because dissolved concentrations should never exceed total concentrations.
- Any data points noted to have potential transcription error, anomalous, and omitted data will be flagged.

All data points that pass the criterion listed above will be entered into the project database. Potential data limitations include, but are not limited to (AMEC 2010):

- Unreported values
- Measurement procedure uncertainty
- Detection limits that change throughout the analytical period
- Small sample size
- Sample outliers
- Improper quality control procedures
- Improper data validation procedures
- Improper data presentation/transcription

Data with limitations are still suitable for analysis given that the user considers the limitations (AMEC, 2010).





### 9.0 References

- AMEC Geomatrix, Inc., "Sampling and Analysis Plan for Evaluating Potential Sources of Low-Level Petroleum Hydrocarbon Compound Detections," November 2010.
- Arizona Department of Mines and Mineral Resources File Data (ADMMR), "Arizona Magma," September 1995.
- CDM Federal Programs Corporation, "Final Sampling and Analysis Plan for Surface Water, Groundwater, and Surface Soil and Waste Rock Sampling," September 2009.
- EPA A, "Method 6200: Field Portable X-Ray Fluorescence Spectrometry For the Determination of Elemental Concentrations in Soil and Sediment," Revision 0, February 2007.
- EPA B, "Method 3050B: Acid Digestion of Sediments, Sludges, and Soils," Revision 2, December 1996.
- Minnesota Department of Health (MDH), "Sampling Handling and Transit Requirements for Arsenic, Total Coliform Bacteria, and Nitrate in New Wells," January, 2013.
- NAU, "Research Services and Facilities," 2016. [Online]. Available: https://nau.edu/Research/Services-Facilities/Labs-Facilities/CPAL/EAL/Services/
- Royal Society of Chemistry. "Atomic Absorption Spectrometry". [Online]. Available: http://www.liskeard.cornwall.sch.uk/images/Liskeard-Sixth-Form/Atomic-Absorption-Spectrometry.pdf
- Stroh, Michael, and John Weber. "Sampling and Analysis Plan for the Viburnum Trend Lead Mining District Transition Zone Assessment Study," Missouri Department of Natural Resources and U.S. Fish and Wildlife Services, 2012, pp. 1-44.
- Versar, "Sampling and Analysis Plan Firing Range Engineering Evaluation/Cost Analysis," October, 2014.
- Zielske E., BLM Client interview, September 7, 2016.





# Appendix B

### Health and Safety Plan AZ Magma Mine Site

# **1.0 Introduction**

This plan has been prepared for implementation by Magma Consulting personnel using operating procedures for which they are appropriately trained. This plan describes lines of authority, site information, safety control measures, and emergency information.

# 2.0 Key Personnel

Eric Zielske is the site supervisor and Bureau of Land Management (BLM) person-in-charge and is responsible for overseeing all operations. Bridget Bero is the Northern Arizona University (NAU) person-in-charge and is responsible for overseeing all NAU student personnel. NAU student personnel include Naser Alqaoud, David Finley, Josue Juarez, and Jessica Szaro.

# 3.0 Hazard Analysis

Information regarding the site and its risks are detailed in Table B-1, the Job Hazard Analysis. The purpose of the Job Hazard Analysis is to identify and evaluate the health and safety hazards associated with each site task. Appropriate control methods are selected to eliminate or control the identified risks. Responses to potential hazards are described in Sections 3.1, 3.2, and 3.3.

	Job Infor	mation			
Phase Description:	Preliminary Assessme	nt/Site Inspection			
Tasks:	Sampling - surface soil				
Location:	Arizona Magma Mine; Chloride (Mohave County), Arizona				
Sampling Start Date:	01/20/2017	Sampling End Date:	01/21/2017		

Table B-1. Job Hazard Analysis





Pote	ntial Hazards During th	is Task and/or Operatio	n
Chemical	Physical	Biological	Radiological
- Lead (Pb) - Arsenic (As)	- Heat stress - Falls	- Animals - Insects - Plants	n/a
Hazard Con	trol Measures Used Du	uring this Task and/or O	peration
Administrative Controls:		erating procedures for soil e disposal, and XRF use. information.	
Engineering Controls:	none		
PPE Description:	Com	oonent	Notes
	Dust mask		
	Disposable white Tyve	k coveralls	
	Safety glasses		
	Disposable shoe cover	S	
	Nitrile gloves		
Dress Code:	Com	oonent	Notes
	Hat		
	Boots		
	Long-sleeve shirt		
	Pants		
	Sunglasses		





Emergency Equipment:	Component	Notes
	First aid kit	

#### 3.1 Responses to Heat Stress

To avoid the symptoms of heat stress (fatigue, headache, profuse sweating), personnel should do the following:

- Drink plenty of water
- Avoid fluids containing caffeine
- Take moments to rest and cool down

If a person experiences symptoms of heat stress or heat exhaustion, they should employ the following responses:

- Remove tight or unnecessary clothing
- Enter a shaded area
- Take small sips of water every 30 seconds to 1 minute

Should the person not respond positively to the actions listed above, refer to Section 6.0 for emergency information and hospital directions.

#### 3.2 Avoiding Falls

To avoid falls that may result in injury, personnel should look where they are stepping before moving forward and employ the buddy system. If a harmful fall does occur, refer to Section 6.0 for emergency information and hospital directions.

#### 3.3 Encounters with Plant and Animal Life

To avoid potentially harmful encounters with plant and animal life at the site, personnel should be fully aware of their surroundings at all times during the investigation and employ the buddy system. Plant and animal life that may be seen at the site include cactus and snakes. Should a harmful encounter occur, refer to Section 6.0 for emergency information and hospital directions.

## 4.0 Required Training

This section identifies necessary trainings for all personnel to work safely on the site. Training requirements are based on the Job Hazard Analysis and relevant Occupational Health and Safety





Administration (OSHA) standards. Personnel who have not completed the training are not permitted to participate in field activities. Required trainings for this site inspection include the following:

- 40-hour initial Hazardous Waste Operations and Emergency Response (HAZWOPER)
- NAU Chemical Hygiene training
- NAU Field Safety training

# **5.0 Decontamination Procedures/Solutions**

This section describes decontamination procedures for all personnel, equipment, and instruments. These procedures help minimize the contact and transfer of contaminants outside of the waste site. Decontamination procedures for this site inspection include the following:

- Personnel: Gloves, shoe covers, and Tyvek coveralls will be placed in a garbage bag and returned to NAU for proper disposal.
- Equipment: Decontaminated on-site and returned to the NAU campus.

## 6.0 Emergency Information

The nearest hospital to the waste site is the Kingman Regional Medical Center (KRMC), approximately 30 minutes away by car. The hospital's address and phone number are listed in Table B-2.

Table B-2. KRMC Contact Information

Address:	3269 Stockton Hill Rd, Kingman, AZ 86409
Phone:	(928) 757-2101

Directions from the waste site to the hospital are detailed in Table B-3.

1.	Drive south from waste site until reaching Co Hwy 125
2.	Turn right onto Co Hwy 125, continue to US-93 South
3.	Turn left onto US-93 South, continue to Kingman
4.	Turn left at US-93 South/I-40 East toward Flagstaff
5.	Continue to exit 51 for Stockton Hill Rd
6.	Continue to Sycamore Ave, take a u-turn
7.	Continue to Kingman Regional Medical Center on right

#### Table B-3. Directions from AZ Magma Mine to KRMC





A map of the drive from the AZ Magma Mine to Kingman is presented in Figure B-1.




Figure B-1. Map from AZ Magma Mine to KRMC