Capstone: SR-64 Preliminary Passing Lane Addition Design

CENE486C 04/26/2019

Christian Hillebrand, Benjamen Ruth Mohammad Ali, Kyle MacPetrie

Purpose:

Design a passing lane 3 miles in length Reduce traffic collisions Alleviate traffic congestion

- Client:
- Arizona Department of Transportation (ADOT).
- Representative:
- Nathan Reisner P.E.
- <u>NReisner@azdot.gov</u>
- 1801 S. Milton Road, Flagstaff AZ, 86001 (928) 779-7545

- Project Exclusions
 - Surveying
 - Geotechnical Analysis

2

New Culvert Design

SR 64 Location (B)

State Location (A)



Figure 1: Project location Map[1]



40

60

80

Miles

20



Map (A) reprsents that SR 64 is located in the state of Arizona in the Coconino County

Map (B) representst the layout of SR 64 between Williams, and the Grand Canyon, and the location of the of the project site.

Legend



Impacts

- Safety
 - 0-0.35 crashes per million vehicle miles traveled between MM201-204[2]
- Time
 - Less travel time
- Economy
 - Fewer Crashes
 - Fewer Police Reports
 - Fewer Emergency Responses
 - Fewer Road Cleaning/ Fixing



Figure 2: Stuck Behind Slow Vehicle [3]

Project Milestones

1. Site Assessment (30 Percent)

- 2. Hydrology and Hydraulics Analysis (60 Percent)
- 3. Existing Highway Design (60 Percent)
- 4. Traffic Control Plan (90 Percent)

5. Design Plan Sets (90 Percent)

- Typical Roadway Sections
- Geometric Control
- Drainage Plans and Details
- Plan and Profile
- Cross Sections
- Traffic Control Plans and Quantities
- Cost Report
- Drainage Report

6. Project Management (90 Percent)

Site Assessment

- Existing Road Condition
- Drainage Condition
- Pavement Assessment
 - Entering *Taper Length* = *Lane Width* * 25
 - ADOT Roadway Design Guidelines- May 2012 Edition- DOC 31-089 (Section 207-B)[4]
 - Dropping Taper Length = Lane Width * Design Speed
 - ADOT Roadway Design Guidelines- May 2012 Edition- DOC 31-089 (Section 207-C)[4]
- Right of Way Assessment
 - Based on the Arizona Highway Department Right of Way Division for State Route 64, Mile Post 200-215 have 100 feet of Right of way on each side of the centerline.[5]



Figure 3: Northbound Mile Marker 201 View



Figure 4: 78" Corrugated Metal Pipe Culvert A

Figure 5: 36" Corrugated Metal Pipe Culvert I



Figure 6: 10'x6' Single Box Concrete Culvert H

Figure 7: 8'x4' Doubled Box Concrete Culvert F



Culvert Analysis

Equation 1: Soil and Cover Conditions

$$S = \frac{1000}{CN} - 10$$

Equation 2: Total Losses From Soil and Cover Conditions $I_a = 0.2S$

Equation 3: Runoff of Water in Inches

$$Q = \frac{(P - I_a)^2}{(P - I_a) + S}$$

Equation 4: Flow Volume

$$Q_t = \frac{Q \times A}{t}$$

Equation 5: Rational Method

$$Q_R = CiA$$

- S= Potential max retention after runoff begins
- CN= Curve number [9]
- I_a = Initial abstraction
- Q= Runoff of water
- P= Precipitation of rainfall for area of interest
- Q_t = Total runoff of water, volume
- A= Area of sub-watershed
- t= Storm time duration
- Q_R = Peak discharge
- C= Runoff coefficient
- i= Design storm rainfall intensity

Culvert Analysis

Table 1: Culvert Analysis for Existing Conditions

				Outputs				
Culvert	Discharge	Max Allowable HW	Shape	Material	Size	Length	Computed HW	
	(cfs)	(ft)				(ft)	(ft)	
A	426.6175	8.5	Circular	CMP	78"	52.0	11.69	Fail
В	5.137906	4.0	Circular	CMP	30"	42.5	2.36	Pass
С	2.159898	8.5	Circular	CMP	30"	68.0	2.06	Pass
D	2.697454	3.8	Circular	CMP	24"	57.0	2.42	Pass
E	1.829324	3.0	Circular	CMP	24"	45.0	1.91	Pass
F	38.98193	6.5	Вох	Concrete	8 x 4 ft	39.5	1.91	Pass
G	4.064084	8.0	Circular	CMP	30"	87.0	2.92	Pass
Н	604.0946	14.0	Вох	Concrete	10 x 6 ft	70.0	10.27	Pass
	2.77633	5.0	Circular	CMP	36"	65.0	2.42	Pass
J	1.290884	3.0	Circular	CMP	24"	54.0	2.62	Pass

Culvert Analysis

Table 2: Culvert Analysis for Post-Construction

			Inputs				Outputs	
Culvert	Discharge	Max Allowable HW	Shape	Material	Size	Length	Computed HW	
	(cfs)	(ft)				(ft)	(ft)	
Α	426.6175	8.5	Вох	Concrete	8 x 4 ft	74.5	6.19	Pass
В	5.137906	4.0	Circular	CMP	30"	62.1	2.31	Pass
С	2.159898	8.5	Circular	CMP	30"	86.2	2.06	Pass
D	2.697454	3.8	Circular	CMP	24"	78.3	2.42	Pass
E	1.829324	3.0	Circular	CMP	24"	60.8	1.92	Pass
F	38.98193	6.5	Вох	Concrete	8 x 4 ft	54.1	2.4	Pass
G	4.064084	8.0	Circular	CMP	30"	117.4	2.92	Pass
Н	604.0946	14.0	Вох	Concrete	10 x 6 ft	87.9	10.27	Pass
	2.77633	5.0	Circular	CMP	36"	87.5	2.42	Pass
J	1.290884	3.0	Circular	CMP	24"	69.6	2.62	Pass

CulvertMaster Software Analysis

Solve For: He	eadwater Elevation	•			
Culvert			_ Inverts		
	Discharge: 426.62	cfs	Invert Upstream:	1.00	ft
Maximum Allo	wable HW: <mark>8.50</mark>	ft	Invert Downstream:	0.00	ft
Tailwate	r Elevation: 1.30	ft	Length:	52.00	ft
Section			Slope:	0.019231	ft/ft
Shape:	Circular	-	Headwater Elevation	ons	
Material:	CMP	•	Maximum Allowab	le: 8.50	ft
Size:	78 inch	•	Computed Headwat	er: 11.69	ft
Number:	1		Inlet Contr	ol: 11.69	ft
Mannings:	0.024	-	Outlet Contr	ol: 11.14	ft
Inlet			Exit Results		
Entrance:	Headwall	•	Discharge: 426.	52	cfs
Ke:	0.50		Velocity: 14.2	8	ft/s
,		di.	Depth: 5.49		ft

olve For: H	eadwater Elevation	-			E
Culvert			- Inverts		
	Discharge: 426.62 cfs	s	Invert Upstr	ream: 1.00	ft
Maximum Allo	wable HW: 8.50 ft		Invert Downstr	ream: 0.00	ft
Tailwate	r Elevation: 1.30 ft		Le	ngth: 74.50	ft
Section			S	ilope: 0.013423	ft/ft
Shape:	Box		Headwater El	evations	
Material:	Concrete 🔹		Maximum Al	lowable: 8.50	ft
Size:	8 x 4 ft 💌		Computed Hea	adwater: 6.19	ft
Number:	2		Inlet	Control: 5.78	ft
Mannings:	0.013 💌	1	Outlet	Control: 6.19	ft
nlet			Exit Results		
Entrance:	0° wingwall flares	•	Discharge:	426.62	cfs
Ke:	0.70		Velocity:	13.08	ft/s
		-1	Depth:	2.04	ft

Figure 11: Culvert A Double-Box 8x4ft Design

Figure 10: Culvert A CMP 78" Design



14



Digital Elevation Model (DEM) and Contours Using ArcGIS





Figure 14: ArcGIS Generated Contour Map[1]

Contour Surface with Alignment



- The alignment is
 - 4.7 miles in length
- A total of 200 foot
 - wide Right of Way
- 3 Intersections
 - located in the
 - project site

Figure 15: Civil 3D Contour Surface with Alignment [7]





Figure 19: Plan and Profile Sheet Sta. 168+50-180+50 [7]







Figure 20: Station 62+00 Cross Section [7]



Figure 21: Station 64+00 Cross Section View [7]

Traffic Control Plan

Table 3: Sequences of Construction

	MA	INTENANCE OF CONSTRUCTION SEQUENCE	
ACTIVITY			
NUMBER	CONSTRUCTION ACTIVITY	TRAFFIC CONTROL	COMMENTS
			Sings are to be placed on embedded posts for the
1	Mobilization, signage and barrier setup	Traffic Control as shown in Detailed SA-3 Traffic Plan	duration of the project
			This activity will have to be started early, to ensure
			that at least on lane is open to traffic. Contractor shall
2	Clearing and Grubbing	Traffic Control as shown in Detailed SA-3 Traffic Plan	maintain traffic control during night
			The Contractor shall maintain at least one lane of
3	Culvert Extension/Replacement, Rough Grade (Cut and Fill)	Traffic Control as shown in Detailed SA-3 Traffic Plan	traffic at all times
			The Contractor shall maintain at least one lane of
4	Placement of ABC Subgrade	Traffic Control as shown in Detailed SA-3 Traffic Plan	traffic at all times
			The Contractor shall maintain at least one lane of
5	Final Grade (ABC)	Traffic Control as shown in Detailed SA-3 Traffic Plan	traffic at all times
			The Contractor shall maintain at least one lane of
6	AC Placement (Asphaltic Concrete)	Traffic Control as shown in Detailed SA-3 Traffic Plan	traffic at all times
			The Contractor shall maintain at least one lane of
7	Signage and Stripping	Traffic Control as shown in Detailed SA-3 Traffic Plan	traffic at all times
			The contractor is responsible for the proper removal
8	Demobilization, Removal of signage and barriers	Traffic Control as shown in Detailed SA-3 Traffic Plan	of signs

Traffic Control Plan

Table 4: Traffic Quantities

	APPR	OXIMA	TE TRAF	IC CONT	ROL QU	ANTITIES	5	-	-		
ITEN <i>A</i> #	ITEM	ACTIVITY NUMBER									τοται
		1	2	3	4	5	6	7	8	UNIT	IUIAL
	ESTIMATED DAYS IN USE	3	30	50	15	16	65	16	3		
	Temporary Concrete										
7016020	Barrier (In Use)	34080	340800	681600	85200	170400	937200	119280	34080	LF-Day	2402640
	Barricade (Type III, High										
7016031	Level Flag Trees)	4	40	80	10	20	110	14	4	EA-Day	282
7016032	Portable Sign Stand (Rigid)	20	200	400	50	100	550	70	20	EA-Day	1410
7016035	Warning Lights (Type A)	150	1500	3000	375	750	4125	525	150	EA-Day	10575
7016039	Embedded Sign Post	4	40	80	10	20	110	14	4	EA-Day	282
7016067	Changeable Message Board	6	60	100	30	32	130	32	6	EA-Day	396
7016071	Pilot Vehicle With Driver	72	720	1200	360	384	1560	384	72	Hour	4752
7016075	Flagging Services (Civilian)	72	720	1200	360	384	1560	384	72	Hour	4752

Traffic Control Plan

Detailed SA-3 Traffic Plan





Cost of Project Implementation

Table 5: Cost of Passing Lane Construction

	Item Description	Unit	Planned Qty.	Unit Price (2008)	Unit Price (2019)	Amount
2010011	Clearing and Grubbing	ACRE	18	\$ 1,600	\$ 3,731	\$67,833
2020038	Removal of Asphaltic Concrete Pavement	CU. YD.	5867	\$ 4	\$9	\$54,724
3030022	Aggregate Base, Class 2	CU. YD.	16427	\$ 45	\$ 105	\$1,723,815
4040111	Bituminous Tack Coat	TON	20	\$ 450	\$ 1,049	\$20,988
4040116	Apply Bituminous Tack Coat	HOUR	50	\$ 140	\$ 326	\$16,324
4040264	Asphalt Binder (PG 64-22)	TON	307	\$ 550	\$ 1,283	\$393,758
4160004	Asphaltic Concrete (3/4" Mix) (End Product)	TON	10980	\$ 43	\$ 100	\$1,101,030
5010011	CMP, 24"	L. FT.	74	\$ 75	\$ 175	\$13,004
5010017	CMP, 30"	L. FT.	81	\$ 85	\$ 198	\$16,119
5010019	CMP, 36"	L. FT.	22	\$ 95	\$ 222	\$4,896
2030301	Roadway Excavation	CU. YD.	2000	\$ 15	\$ 35	\$69,960
6010002	Structural Concrete (Class S)	CU. YD.	28	\$ 650	\$ 1,516	\$42,670
7016020	Temporary Concrete Barrier (In Use)	LF-DAY	2402640	\$ 0.20	\$ 0.47	\$1,120,591
7016031	Barricade (Type III, High Level Flag Trees)	EACH-DAY	282	\$ 1	\$ 2	\$658

Cost of Project Implementation

Table 5: Cost of Passing Lane Construction (Continued)

	Item Description	Unit	Planned Qty.	Unit Price (2008)	Unit Price (2019)	Amount
7016032	Portable Sign Stands (Rigid)	EACH-DAY	1410	\$ 1	\$ 2	\$3,288
7016035	Warning Lights (Type A)	EACH-DAY	10575	\$ 0.25	\$ 1	\$6,165
7016039	Embedded Sign Post	EACH-DAY	282	\$ 0.15	\$ 0.35	\$99
7016067	Changeable Message Board	EACH-DAY	396	\$ 25	\$ 58	\$23,087
7016071	Pilot Vehicle with Driver	HOUR	4752	\$ 40	\$ 93	\$443,267
7016075	Flagging Services (Civilian)	HOUR	4752	\$ 22	\$ 51	\$243,797
7060101	Pavement Marker, Recessed, Type D	EACH	792	\$5	\$ 12	\$9,235
7080001	Permanent Pavement Marking (Painted)	L. FT.	17040	\$ 0.15	\$ 0.35	\$5,961
9240170	Contractor Quality Control	L. SUM		\$ 49,000	\$ 114,268	\$114,268
9240183	Miscellaneous Work (Seal Cracks)	LB.	350	\$ 3	\$6	\$2,041
9250001	Construction Surveying and Layout	L. SUM		\$ 34,000	\$ 79,288	\$79,288
	Embankment	CU.YD.	28000	\$ 19	\$ 45	\$1,260,000
9280036	Ground-In Rumble Strip (8 in.)	L. FT.	17040	\$ 0.20	\$ 0.47	\$7,947
					Total Price	\$6,844,812
	Construction Engineering	% of Total			14	\$958,274
	Construction Design Services	% of Total			1	\$68,448
	Contingency	% of Total			5	\$342,241
					Total Project Cost	\$8,213,774

SR-64 Critical Path

Task Name	Duration	Start	Finish	12	February 2019	11 16 21	March 2019	13 18 23 28	April 2019	May 2019	12 17
1 Site Assessment	2 days	Mon 1/14/19	Tue 1/15/19	•	1		n	12 1 10 1 22 1 20			
1.1 Road Condition Assessment	2 days	Mon 1/14/19	Tue 1/15/19								
1.1.1 Asphalt Condition	2 days	Mon 1/14/19	Tue 1/15/19	= '							
1.1.2 Shoulder Condition	2 days	Mon 1/14/19	Tue 1/15/19	= '							
1.2 Drainage Condition Assessment	2 days	Mon 1/14/19	Tue 1/15/19								
1.2.1 Culvert Condition and Location	2 days	Mon 1/14/19	Tue 1/15/19	= '							
1.2.2 Wash Integrity	2 days	Mon 1/14/19	Tue 1/15/19								
1.3 Soil Sampling	2 days	Mon 1/14/19	Tue 1/15/19	-							
1.4 Right of Way Assessment	2 days	Mon 1/14/19	Tue 1/15/19								
2 Hydrology and Hydraulics Analysis	30 days	Wed 1/16/19	Tue 2/26/19	F			2/26				
2.1 Map Culverts	10 days	Wed 1/16/19	Tue 1/29/19	/							
2.2 Hydrology	10 days	Wed 1/30/19	Tue 2/12/19		*	h					
2.3 Hydraulics	10 days	Wed 2/13/19	Tue 2/26/19			*					
3 Geotechnical Analysis	20 days	Wed 1/16/19	Tue 2/12/19	r	*	2/12	1	+			
4 Highway Design	13 days	Wed 2/27/19	Fri 3/15/19								
4.1 Cross Sections	13 days	Wed 2/27/19	Fri 3/15/19				*				
5 Traffic Control Plan	14 days	Wed 2/6/19	Mon 2/25/19				2/25				
6 Design Plan Sets	83 days	Wed 1/16/19	Fri 5/10/19	r							5/10
6.1 Face Sheet	10 days	Wed 1/16/19	Tue 1/29/19	1	*						
6.2 Roadway Sections Plan Sheets	15 days	Mon 3/18/19	Fri 4/5/19					+			
6.3 Existing Conditions Plan Sheets	15 days	Wed 1/16/19	Tue 2/5/19	1	*		↓				
6.4 Structural Plan Sheets	15 days	Mon 3/18/19	Fri 4/5/19					+			
6.5 Drainage Plan Sheets	15 days	Mon 4/8/19	Fri 4/26/19						+	_	
6.6 SWPPP Sheet	15 days	Wed 2/27/19	Tue 3/19/19				*				
6.7 Traffic Control Plan Sheets	10 days	Tue 2/26/19	Mon 3/11/19				₩				
6.8 Cost Estimate Report Sheet	83 days	Wed 1/16/19	Fri 5/10/19	r							5/10
6.8.1 Scoping	20 days	Wed 1/16/19	Tue 2/12/19	Ĩ	*						
6.8.2 Preliminary Engineering Design	63 days	Wed 2/13/19	Fri 5/10/19		r						•
6.8.2.1 Plan Sheets	10 days	Mon 4/29/19	Fri 5/10/19							*	
6.8.2.3 Drainage Report	10 days	Mon 4/29/19	Fri 5/10/19							+	
6.8.3 Construction Implementation	10 days	Wed 1/16/19	Tue 1/29/19	r r	1						
6.8.4 Mobilization and Administration Costs	44 days	Wed 1/16/19	Mon 3/18/19	r r							27
7 Project Management	85 days	Mon 1/14/19	Fri 5/10/19								· · ·

ID	Task Name	Duration	Start	Finish	February 2019 March 2019 April 2019 May 20 27 1 6 11 16 21 26 3 8 13 18 23 28 2 7 12 17 22 27 2	019
1	1 Site Assessment	2 days	Tue 1/29/19	Wed 1/30/19	1/20/10	s die der s
2	1.1 Road Condition Assessment	2 days	Tue 1/29/19	Wed 1/30/19		
5	1.2 Drainage Condition Assessment	2 days	Tue 1/29/19	Wed 1/30/19		
8	1.3 Right of Way Assessment	2 days	Tue 1/29/19	Wed 1/30/19	3/13/19	
9	2 Hydrology and Hydraulics Analysis	30 days	Thu 1/31/19	Wed 3/13/19		
10	2.1 Map Culverts	10 days	Thu 1/31/19	Wed 2/13/19		
11	2.2 Hydrology	25 days	Thu 1/31/19	Wed 3/6/19		
12	2.3 Hydraulics	5 days	Thu 3/7/19	Wed 3/13/19	4/3/19	
13	3 Highway Design	20 days	Thu 3/7/19	Wed 4/3/19		
17	4 Traffic Control Plan	5 days	Tue 4/9/19	Mon 4/15/19		
21	5 Design Plan Sets	42 days	Thu 3/7/19	Fri 5/3/19		
22	5.1 Face Sheet	5 days	Thu 4/4/19	Wed 4/10/19		s/3/19
23	5.2 Typical Roadway Sections Sheet	3 days	Wed 4/10/19	Fri 4/12/19		
24	5.3 Geometric Control Sheet	5 days	Thu 4/18/19	Wed 4/24/19		
25	5.4 Existing Conditions and Removal Sheet	20 days	Tue 3/26/19	Mon 4/22/19		
26	5.5 Roadway Plan and Profile Sheets	40 days	Thu 3/7/19	Wed 5/1/19	→I I I I I I I I I I I I I I I I I I I	
27	5.6 Drainage Plans and Details Sheets	25 days	Thu 3/28/19	Wed 5/1/19	*	
28	5.7 Intersection Plans and Details	20 days	Thu 3/7/19	Wed 4/3/19		
29	5.8 Traffic Control Plan Sheets	5 days	Tue <mark>4/9/1</mark> 9	Mon 4/15/19		
32	5.9 Roadway Cross Section Sheets	5 days	Thu 4/18/19	Wed 4/24/19		
33	5.10 Cost Estimate Report Sheet	20 days	Thu 4/4/19	Wed 5/1/19		
34	5.10.3.1 Site Obstruction Removal	20 days	Thu 4/4/19	Wed 5/1/19		
35	5.10.3.2 Excavation, Backfill, Embankment	20 days	Thu 4/4/19	Wed 5/1/19		
36	5.10.3.3 Construction	20 days	Thu 4/4/19	Wed 5/1/19	*	
37	5.11 Drainage Report- Roadway	37 days	Thu 3/14/19	Fri 5/3/19		
38	5.12 Drainage Report- Structures	37 days	Thu 3/14/19	Fri 5/3/19		5/3/10
39	6 Project Management	69 days	Tue 1/29/19	Fri 5/3/19		28

Previous Staffing Hours

Table 6: Old Staffing Plan

		STAFF (hours)		
Task Name	Project	Senior	Engineer	Draftor	Task Total
	Manager	Engineer	Step I	Draiter	
1 Site Assessment	30	30	20	32	112
2 Hydrology and Hydraulics Analysis	0	12	18	24	54
3 Geotechnical Analysis	0	35	45	0	80
4.0 Highway Design	26	21	29	50	126
5 Traffic Control Plan	36	0	0	0	36
6 Design Plan Sets	102	106	88	88	384
6.1 Face Sheet	8	4	4	12	28
6.2 Roadway Sections Plan Sheets	0	10	10	10	30
6.3 Existing Conditions Plan Sheets	0	10	10	10	30
6.4 Roadway Construction Plan Sheets	0	10	10	10	30
6.5 Drainage Plan Sheets	0	10	20	20	50
6.6 SWPPP Sheet	0	10	0	10	20
6.7 Traffic Control Plan Sheets	2	12	6	16	36
6.8 Cost Estimate Report Sheet	92	40	28	0	160
7 Project Management	47	45	55	47	194
STAFF TOTAL	194	204	200	241	839

Current Staffing Hours

Table 7: Current Staffing Plan

		STAFF (ho	ours)		
Task Name	Project	Senior	Engineer	Draftar	Task Total
	Manager	Engineer	Step I	Draiter	
1 Site Assessment	11	13	14	12	50
2 Hydrology and Hydraulics Analysis	12	17	24	23	76
3 Highway Design	15	22	24	52	113
4 Traffic Control Plan	8	13	12	10	43
5 Design Plan Sets	86	107	87	143	423
5.1 Face Sheet	3	4	3	8	18
5.2 Roadway Sections Plan Sheets	7	7	6	20	40
5.3 Existing Conditions Plan Sheets	5	6	6	18	35
5.4 Structural Plan Sheets	7	7	10	9	33
5.5 Drainage Plan Sheets	8	8	5	16	37
5.6 Traffic Control Plan Sheets	5	6	5	16	32
5.7 Cost Estimate Report Sheet	51	69	52	56	228
6 Project Management	20	20	20	20	80
STAFF TOTAL	152	192	181	260	785

Engineering Cost

Billable Services								
Staff	Hours	Cost	t per Hour	Cost Per Staff				
Project Manager	194	\$	140	\$	27,160			
Senior Engineer	204	\$	112	\$	22,848			
Engineer Step I	200	\$	34	\$	6,800			
Drafter	241	\$	36	\$	8,676			
Totals	839			\$	65,484			

Table 8: Initial Cost Estimate for Staff Members/Total Hours

Table 9: Final Cost for Staff Members/Total Hours

Totals	785			\$	58,298			
Drafter	260	\$	36	\$	9,360			
Engineer Step I	181	\$	34	\$	6,154			
Senior Engineer	192	\$	112	\$	21,504			
Project Manager	152	\$	140	\$	21,280			
Staff	Hours	Cost per Hour		Cost Per Staff				
Billable Services								

Table 10: Billing Rates of Staff Involved with the Project

Billing Rates								
Staff	Cost	per Hour	Benefits (%)	Profit (%)	Cos	t Per Hour		
Project Manager	\$	129	30	10	\$	181		
Senior Engineer	\$	80	30	10	\$	112		
Engineer Step I	\$	24	30	10	\$	34		
Drafter	\$	26	30	10	\$	36		

Conclusion

- The passing lane is 3 miles in length
 - Between Marker 201 and Marker 204
- Culvert A must be replaced before construction.
- 9 Culverts need to be extended.
- The total cost for constructing the lane is \$8,213,000
- Total project duration is 198 days, 141 working days

References

- [1] ARCGIS Software. (2001). Redlands, CA: Esri.
- [2] Engineering, Jacobs, "Final Feasibility Report State Route 64: I-40 to Moqui Williams Grand Canyon -Cameron Highway," Arizona Department of Transportation, Phoenix, Arizona , March 2006.
- [3] "How Do You React to Being Stuck Behind Slow-Moving Trucks?," *Carolyn's Online Magazine*, 31-May-2015. [Online]. Available: https://carolynsonlinemagazine.wordpress.com/2015/05/30/how-doyou-react-to-being-stuck-behind-slow-moving-trucks/. [Accessed: 25-Apr-2019].
- [4] Arizona Department of Transportation, "ARIZONA DEPARTMENT OF TRANSPORTATION," May 2014. [Online]. Available: https://www.azdot.gov/docs/default-source/business/roadway-designguidelines.pdf?sfvrsn=8. [Accessed 8 February 2019].
- [5] Arizona Right of Way Division, "Arizona Department of Transportation," 6 June 1946. [Online]. Available: https://www.azdot.gov/files/ROW/Plans/State_Route_64/3-T-291.pdf. [Accessed February 2019].
- [6] JE Fuller Hydrology and Geomorphology Inc., "AZ Department of Transportation," January 2014. [Online]. Available: https://www.azdot.gov/docs/default-source/roadway-engineering-library/2014_adot_hydrology_manual.pdf?sfvrsn=6. [Accessed 8 February 2019].
- [7] AutoCAD Civil3D Software.
- [8] Arizona Department Of TRANSPORTATION, "TRAFFIC CONTROL DESIGN GUIDELINES 2010," ADOT, 2011.
- [9] Division, Conservation Engineering, "Urban Hydrology for Small Watersheds TR-55," United States Department of Agriculture, June 1986.