




**Construction Notes**

①	UF	123	INSTALL 4-INCH SEWER SERVICE LINE (PVC) SDR-35, INCLUDING ALL APPURTENANCES PER DETAIL B ON SHEET 2. TRENCH, EXCAVATION, BACKFILLING, AND COMPACTION PER C.O.F. STD. DTL. 9-01-032 ON SHEET 2.
②	UF	560	INSTALL 12-INCH (PVC) SDR-35, INCLUDING ALL APPURTENANCES PER DETAIL B ON SHEET 2. TRENCH EXCAVATION, BACKFILLING, AND COMPACTION PER C.O.F. STD. DTL. 9-01-030, AND 9-01-032 ON SHEET 2.
③	EA	2	INSTALL 48" DIA. SEWER MANHOLE. SEE DETAIL D ON SHEET 3. INSTALL 24" FRAME & COVER PER M.A.G. STD. PER M.A.G. DTL. 422 ON SHEET 4.
④	EA	1	INSTALL 4" SEWER SERVICE CONNECTION. REFER TO SHEET 8 FOR SEWER SERVICE PROFILES.
⑤	SF	127	REMOVE AND REPLACE ASPHALT PAVEMENT PER C.O.F. STD. DTL. 9-01-030 ON SHEET 2.
⑥	UF	4	REMOVE AND REPLACE VERTICAL CURB AND GUTTER PER DETAIL A ON SHEET 2.

NOTES:  
 1. INSTALL TRACER WIRE ALONG ALL SEWER LINES AND SERVICE LINES PER C.O.F. STD. DTL. 9-01-020 ON SHEET 4.



COPPERMINE ROAD  
 SEWER PLAN

DRAWN BY: COURTNEY FREEMAN  
 CHECKED BY: ANDREW SINGER  
 DATE: 10/20/2020  
 SCALE: 1"=40'

NO.	DATE	COMMENTS
1	11/5	



**Team Outlier Engineering**  
 Civil Engineering, Construction  
 Management and Environmental Engineering

~SHEET~  
 6 OF 10