

Codes & Regulations Applied

- Avoid winter construction from October 1 through April 1, and possibly the monsoon season during August.
- Grade checks will be done to ensure the slope of the property does not exceed 3%, which is the ideal slope to avoid erosion from flow.
- Seeding for native vegetation will be required for post-construction to ensure there is no drop in foliage.
- A temporary gravel entrance/exit will be constructed directly west of the project manhole.
- Dust control will be done by watering the soil during construction to reduce wind erosion.
- Waste management including storage, disposal, and well-maintained toiletries will be installed on the western side of the property.
- Storage must be available for all materials that can contribute pollutants to stormwater.
- Routine inspections must be completed by trained inspectors weekly. The inspection report used can be found in the EPA's guide to developing an SWPPP.
- Straw wattles will be put in place to direct sediment flow into the trench.
- Hay bales below the culvert outlet should be in place during construction.