

Fanning Wash Low-Water Crossing Design



Figure 1: I-40E Existing Culvert [1]

Austin Simmons, Preston Meek, Abdalla Alatar, Muhammad Muhammad

AAMP Engineering Inc.

Introduction

Purpose

- Create design alternatives for the Low-Water Crossing at Fanning Wash & Soliere Rd to mitigate flooding.

Client/Technical Advisor

- Edward Schenk; Project Manager for City of Flagstaff Stormwater Division

Background/Goals

- Improve on various hydraulic factors.
- Create an accurate flow model.
- Proposed culvert designs.




Figure 2: Project Location in relation to Flagstaff, Arizona [1]

Fanning Wash and Soliere Rd. Project Location




Figure 4: Aerial Image of Fanning Wash & Project Location [1]



Figure 3: Erosion at Low-water crossing [1]



Figure 5: Aerial Image of Zoomed in Project location [1]

Scope of Services

Task 1.0: Preliminary Site Research

- Existing I-40 Culvert Research
- Standards and Codes Research

Task 2.0: Field and Lab Work

- **Task 2.1 Site Mapping**
 - Site Inventory
 - Survey Site
 - Create Topographic Map
- **Task 2.2 Geotechnical Analysis**
 - Sampling Plan
 - Sampling
 - Particle Size Distribution and Sieve Analysis
 - Atterberg Limits Test



Figure 6: Sieve Analysis Equipment [2]



Figure 7: Atterberg Limits Equipment [3]

Scope of Services

Task 3.0 HEC-RAS Hydraulic Analysis

Task 4.0 Design Alternatives & Selection of Final Design

- **Task 4.1 Design Alternatives**
- **Task 4.2 Analyze Alternatives**
 - Preliminary Hydraulic Models
 - Decision Matrix
 - Select Final Design

Scope of Services

Task 5.0 Final Design

- Task 5.1 Plan Set Development
- Task 5.2 Construction Cost Estimate

Task 6.0 Impacts

- Environmental
- Economic
- Societal

Scope of Services

Task 7.0: FEMA Floodplain Analysis

- Floodplain analysis post-construction will be discussed.

Task 8.0: Deliverables

- **Task 8.1 30% Submittal**
 - Design Report
 - Presentation
 - Plan Set
- **Task 8.2 60% Submittal**
 - Design Report
 - Presentation
 - Plan Set
- **Task 8.3 90% Submittal**
 - Design Report
 - Presentation
 - Plan Set
 - Website
- **Task 8.2 Final Submittal**
 - Final Report
 - Final Presentation
 - Completed Plan Set
 - Completed Website

Scope of Services

Task 9.0: Project Management

- Task 9.1 Resource Management
- Task 9.2 Team Management and Meetings



Figure 8: Resource Management [4]

Exclusions

- Roadway Design
- Construction
- Unforeseen Site Conditions



Figure 8: Roadway Construction (Flagstaff) [5]

Schedule

ID	Task Mode	Task Name	Duration	Start	Finish	Predecessor	Resource Names	Gantt Chart (September 2021 to December 2021)																											
0		Project Gantt Chart	70 days	Mon 8/30/21	Fri 12/3/21			[Gantt Chart Visualization]																											
1		Task 1: Preliminary Site research	1 day	Mon 8/30/21	Mon 8/30/21			[Gantt Chart Visualization]																											
2		1.1 Existing I-40 Culvert Research	1 day	Mon 8/30/21	Mon 8/30/21			[Gantt Chart Visualization]																											
3		1.2 Standards and Codes Research	1 day	Mon 8/30/21	Mon 8/30/21			[Gantt Chart Visualization]																											
4		TASK 2: Field and Lab Work	6 days	Wed 9/1/21	Wed 9/8/21			[Gantt Chart Visualization]																											
5		2.1 Site Mapping	3 days	Wed 9/1/21	Fri 9/3/21	1		[Gantt Chart Visualization]																											
6		2.1.1 Site Inventory	1 day	Wed 9/1/21	Wed 9/1/21	2		[Gantt Chart Visualization]																											
7		2.1.2 Survey Site	1 day	Thu 9/2/21	Thu 9/2/21	2		[Gantt Chart Visualization]																											
8		2.1.3 Topographic Map	1 day	Fri 9/3/21	Fri 9/3/21	7,6		[Gantt Chart Visualization]																											
9		2.2 Geotechnical Analysis	3 days	Mon 9/6/21	Wed 9/8/21			[Gantt Chart Visualization]																											
10		2.3.1 Sampling Plan	1 day	Mon 9/6/21	Mon 9/6/21			[Gantt Chart Visualization]																											
11		2.3.2 PSD and Sieve Analysis Test	1 day	Tue 9/7/21	Tue 9/7/21	10		[Gantt Chart Visualization]																											
12		2.3.3 Soil Limits Testing	1 day	Wed 9/8/21	Wed 9/8/21	10		[Gantt Chart Visualization]																											
13		TASK 3: Hydraulic Analysis of Existing Crossing	1 day	Mon 9/13/21	Mon 9/13/21			[Gantt Chart Visualization]																											
15		TASK 4: Design Alternatives & Selection of Final	18 days	Mon 9/20/21	Fri 9/29/21			[Gantt Chart Visualization]																											
16		4.1 Develop Alternatives	5 days	Mon 9/20/21	Fri 9/24/21	2,8,14		[Gantt Chart Visualization]																											
17		4.2 Analysis Alternatives	3 days	Mon 9/27/21	Wed 9/29/21			[Gantt Chart Visualization]																											
18		4.2.1 Preliminary Hydraulic Models	1 day	Mon 9/27/21	Mon 9/27/21	16		[Gantt Chart Visualization]																											
19		4.2.2 Decision Matrix	1 day	Tue 9/28/21	Tue 9/28/21	16,3,18		[Gantt Chart Visualization]																											
20		4.2.3 Select Final Design	1 day	Wed 9/29/21	Wed 9/29/21	19		[Gantt Chart Visualization]																											
21		TASK 5: Final Design	8 days	Mon 10/4/21	Wed 10/13/21			[Gantt Chart Visualization]																											
22		5.1 Plan Set Development	4 days	Mon 10/4/21	Thu 10/7/21	20,8,9		[Gantt Chart Visualization]																											
23		5.2 Construction Cost Estimate	4 days	Mon 10/11/21	Thu 10/14/21			[Gantt Chart Visualization]																											
24		Task 6: Impacts of Design	2 days	Mon 10/18/21	Tue 10/19/21	20		[Gantt Chart Visualization]																											
25		Task 7: FEMA Floodplain Analysis	1 day	Mon 10/25/21	Mon 10/25/21	18,20		[Gantt Chart Visualization]																											
26		TASK 8: Deliverables	13 days	Mon 11/1/21	Wed 11/17/21			[Gantt Chart Visualization]																											
27		8.1 30% Submittal	4 days	Mon 11/1/21	Thu 11/4/21	18,22		[Gantt Chart Visualization]																											
32		8.2 60% Submittal	4 days	Mon 11/8/21	Thu 11/11/21	22,27		[Gantt Chart Visualization]																											
37		8.3 90% Submittal	3 days	Mon 11/15/21	Wed 11/17/21	22,32		[Gantt Chart Visualization]																											
43		8.4 Final Submittal	2 days	Mon 11/29/21	Tue 11/30/21	37,24,49,		[Gantt Chart Visualization]																											
49		TASK 9: Project Management	70 days	Mon 8/30/21	Fri 12/3/21			[Gantt Chart Visualization]																											
50		9.1 Resource Management	70 days	Mon 8/30/21	Fri 12/3/21			[Gantt Chart Visualization]																											
51		9.2 Team Management and Meetings	70 days	Mon 8/30/21	Fri 12/3/21			[Gantt Chart Visualization]																											

Project Project Gantt Chart
Date: Wed 4/7/21

Task		Inactive Task		Manual Summary Rollup		External Milestone		Manual Progress
Split		Inactive Milestone		Manual Summary		Deadline		
Milestone		Inactive Summary		Start-only		Critical		
Summary		Manual Task		Finish-only		Critical Split		
Project Summary		Duration-only		External Tasks		Progress		

Staffing Plan

- Chief Engineer (CEN)
- Project Engineer (PEN)
- Intern Engineer (INT)
- Technician (TEC)

Table 1: Summary of Work Hours

Staff	Hours
CEN	141
PEN	166
INT	213
TEC	239
Total	759

Cost of Engineering Services

Table 2: Cost of Engineering Services

	Classification	Hours	Rate, \$/hr	Cost
Personnel	CEN	141	190	26790
	PEN	166	120	19920
	INT	213	75	15975
	TEC	239	60	14340
Supplies	Surveying Equipment Rental	24	100	2400
Cost of Engineering Services Total				79425

References

[1] "Google Maps", *Google Maps*, 2021. [Online]. Available: <https://www.google.com/maps>. [Accessed: 15- Feb- 2021].

[2] 2021. [Online]. Available: <https://basiccivilengineering.com/2017/06/sieve-analysis-test.html>. [Accessed: 08- Apr- 2021].

[3]"Atterberg Limits", *Humboldtmgf.com*, 2021. [Online]. Available: <https://www.humboldtmgf.com/atterberg-limits/>. [Accessed: 08- Apr- 2021].

[4] J. Trout, "Maintenance Management: An Overview," *Reliable Plant*, 01-Apr-2020. [Online]. Available: <https://www.reliableplant.com/maintenance-management-31856>. [Accessed: 07-Apr-2021].

[5] P. Meek, "Photos of SR-89A Deck Construction", [Photographed]. Taken: May 21st, 2020.